



**Hansraj College**  
University of Delhi  
Mahatma Hansraj Marg, Malka Ganj  
Delhi - 110007

**हंसराज महाविद्यालय**  
दिल्ली विश्वविद्यालय  
महात्मा हंसराज मार्ग, मल्कागंज  
दिल्ली 110007

Ref: No. QUOT/DC/2020/20

Date: 20/07/2020

**QUOTATION INVITING NOTICE**

**Sealed quotations are invited for Repair of Column of Class-III Non- Teaching Staff quarter of Hansraj College as per the following specification:**

Sr. No.	Description of Item(s)	Qty.
1	Chipping of existing cement plaster manually from masonry or concrete surface using chisel and hammer disposal of debris within a lead of 50 m complete.	30sqm
2	12mm cement plaster of mix (Junction of all RCC and brick shall be provided with chicken wire mesh of 150mm width on either side of the junction before plastering) 1:1:2 (1cement:3course sand :3fine sand)	30sqm
3	Providing & application of bond coat on the concrete surface by mixing high dispersion SBR latex like Master Emco SBR 2 of BASF with white cement in the ratio of 2:3, The mixing should be done to a lump free consistency for the bond coat and the screed/ mortar should be applied once the bond coat is tacky. Master EMCO SBR 2 of BASF or Nitto bond SBR-2 (Latex) of Fosroc or Equivalent.	30sqm
4.	Cleaning reinforcement of total rust by tapping & using mechanical wire brush or any other suitable way including from behind and around the reinforcement bars to give it totally rust free finished steel surface. Rebacking primer SB-R equivalent (mode of measurement.	20sqm
5.	Providing & supplying the one component, Polymer modified cementitious anti - corrosive primer (having the technical parameters mentioned in material specifications) formulated to provide dual protection of a polymeric barrier and an integral corrosion - inhibiting system , to the existing steel & additional steel provided before patching of damaged areas, using suitable tools and equipment inclusive of Material, Manpower and Equipment. BASF Master Emaco P 130/Fosroc Nitoprime Zincrich / Sika Rustoff 100 or other equivalent.	30sqm
6.	Disposal of excess earth/building rubbish/ malba /similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by engineer-in-charge, beyond 50m initial lead, for all lead including all lifts involved.	2 Trip
7.	Providing and fixing double scaffolding system (cup lock type)on the exterior side up to seven store height made with 40mm dia m.s tube 1.5m center to center horizontal &vertical tube joining with cup &lock system with m.s tube ,ms tube challies,m.s clamps and m.s stair case system in the scaffolding for	80sqm

	working platform etc. And maintaining it in a serviceable condition for the required duration as approved and removing it thereafter.as per direction of engineer-in charge.	
<b>8.</b>	Providing and using single component cement based non -shrink micro concrete of approved manufacture by mixing graded stone aggregate 10mm and down and coarse sand as per manufactures specification & direction of Engineer-in-charge complete as per design and approved by Engineer-in-charge at all floor and all heights.	<b>30sqm</b>
<b>9.</b>	Providing, making fixing &anchoring of reinforcing bars or dowels or rebar including drilling the holes, fixing the bar and grout the bar with Hilty HIT - HY-150 grouting chemical, all labour all tools & plants, necessary scaffolding etc but excluding the reinforcement steel complete for all lead & lift as per directed by Engineer Incharge /structural consultants or Architect. Rebarring depth minimum 300 mm or 20 D whichever is more. 10mm dia	<b>220Nos.</b>
<b>10.</b>	Steel reinforcement of R.C.C work including straightening, cutting banding placing in position and binding all complete up to all level. Thermo-Mechanically Treated bar.	<b>90Kg</b>

- 1. Sealed envelope should be super-scribed with “Repair of Column of Class-III Non- Teaching Staff quarter” and addressed to**

**The Principal,  
Hansraj College  
Malka Ganj  
Delhi-110007**

- 2. Quotation should reach to the above address through Registered/Speed post or by hand latest by 30.07.2020 up to 11:00A.M. And will be open on 30.07.2020 at 2:00 P.M.**
- 3. The unit rate for any item should be quoted without GST and the slab (%) or amount of GST to be mentioned therein**
- 4. Any rate quoted by vendor without mentioning GST slab for any item, the quoted rate for that item will be considered as GST inclusive.**
- 5. Vendors who are applying for above quotation must have GSTIN registration and GSTIN no. to be mentioned on the quotation.**
- 6. The Principal may accept or reject any or all the quotation in part or full without assigning any reason.**
- 7. The Principal reserve the right to splitting the items to two or more vendor for placement of order.**
- 8. Payment Terms: Full and final payment will be made after successful completion of work.**
- 9. All the payment will be made through RTGS/NEFT only.**

<b>-Sd- Convener Development Committee</b>	<b>-Sd- Principal Hansraj College</b>
--	---

**Copy to: College Website**