



**Hansraj College**  
University of Delhi  
Mahatma Hansraj Marg, Malka Ganj  
Delhi - 110007

**हंसराज महाविद्यालय**  
दिल्ली विश्वविद्यालय  
महात्मा हंसराज मार्ग, मल्कागंज  
दिल्ली 110007

Ref: No. QUOT/2020/09

Date: 05/02/2020

**QUOTATION INVITING NOTICE**

Sealed quotations are invited for Repair of Chajja of Class III Non-Teaching Staff Quarter of Hansraj College as per the following specification:

Sr. No.	Description of Item(s)	Qty.
1.	Demolishing bricks work in cement mortar manually by mechanical means including its wall plaster, staking of serviceable materials and disposal of unserviceable within 50 mtr lead as per direction of Engineer-in-charge.	1.5 Cum
2.	Disposal of excess earth/building rubbish/ malba /similar unserviceable ,dismantled or waste materials by mechanical means including loading ,transporting ,unloading to approved municipal dumping ground or as approved by engineer-in-charge, beyond 50m initial lead, for all lead Including all lifts involved.	2 Trip
3.	Bricks work with common burnt clay F.P.S. (non modular ) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and size in : cement mortar 1:6 (1 Cement :6 Coarse sand).as per direction of engineer-in-charge. cement mortar 1:4 (1 cement : 4 course sand)	0.5 Cum
4.	12mm cement plaster of mix (Junction of all RCC and brick shall be provided with chicken wire mesh of 150mm width on either side of the junction before plastering) 1:1:2 (1cement:3course sand :3fine sand)	30 Sqm
5.	Providing and fixing double scaffolding system (cup lock type)on the exterior side up to seven store height made with 40mm dia m.s tube 1.5m center to center horizontal &vertical tube joining with cup &lock system with m.s tube ,m.stube challies,m.s clamps and m.s stair case system in the scaffolding working platform etc. And maintaining it in a serviceable condition for the required duration as approved and removing it thereafter.the scaffolding system shall be stiffened with bracing ,runner connection with the building etc wherever required for inspection of work at required locations with essential safety features for the.	300 Sqm
6.	Providing and fixing horizontal chajja of stone 40 mm thickness and up to 80mm projection in cement mortar 1:4 (1 cement : 4 course sand) including pointing white cement mortar 1:2 (1cement :2stone dust ) with an admixture of pigment matching the red sand stone	30 Sqm
7.	Providing and laying in position machine batched and machine mixed design mixM-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the coats of centering , shuttering ,fining and reinforcement, including admixers in recommended proportions as per Is:910 to acceleratioate ,retard setting of concrete improve workability without impairing strength and durability as per direction of engineer-in-charge. All work above plinth level up to floor V level.	2.5 Cum

8.	Demolishing R.C.C work in columns, Beam, Slabs, staircase waist slab etc. including all covering plaster/flooring etc. manually by mechanical means including staking of steel bar and disposal of unserviceable material within 50mtr lead as per direction of Engineer-in-charge.	2.5 Cum
9.	Structural steel work in single section ,fixed with or without connecting plate, angle, including cutting welding and fixing in position and applying a Priming coat of approved steel primer all complete. M.S Angle 35x35x5,40x40x6mm	400 Kg
10.	Steel reinforcement of R.C.C work including straightening ,cutting banding Placing in position and binding all complete up to all level. Thermo-Mechanically Treated bar. (Only TATA or SAIL).	100 Kg
11.	Providing and applying tape Crete (minium2 coats) water proofing to sunken toilet, balcony, chajja as per manufacture's specification including base plaster & protective cement plater in horizontal and vertical surface-surface to be punned with neat cement complete.	20 Sqm

1. Sealed envelope should be super-scribed with “Quotation for Repair of Chajja of Class III Non-Teaching Staff Quarter” and addressed to

The Principal,  
Hansraj College  
Malka Ganj  
Delhi-110007

2. Quotation should reach to the above address through Registered/Speed post or by hand latest by 14.02.2020 up to 11:00 A.m. and it will open on 14.02.2020 at 12:30 P.m.

4. The unit rate for any item should be quoted without GST and the slab (%) or amount of GST to be mentioned therein.

5. Any rate quoted by vendor without mentioning GST slab for any item, the quoted rate for that item will be considered as GST inclusive.

6. Vendors who are applying for above quotation must have GSTIN registration and GSTIN no. to be mentioned on the quotation.

7. The Principal may accept or reject any or all the quotation in part or full without assigning any reason.

8. The Principal reserve the right to splitting the items to two or more vendor for placement of order.

9. Payment Terms: Full and final payment will be made after successful completion of book binding work.

10. All the payment will be made through RTGS/NEFT only.

-Sd-  
Convener  
Development Committee

-Sd-  
Principal  
Hansraj College

Copy to: College Website