



**Hansraj College**  
University of Delhi  
Mahatma Hansraj Marg, Malka Ganj  
Delhi - 110007

**हंसराज महाविद्यालय**

दिल्ली विश्वविद्यालय  
महात्मा हंसराज मार्ग, मल्कागंज  
दिल्ली 110007

Ref: No. QUOT/Development/2021-22/02

Date: 17.08.2021

**QUOTATION INVITING NOTICE**

**Sealed quotations are invited for Repair of False ceiling, u-shape drain, roof panel (Puff sheet), gypsum ceiling at various places in the Hansraj College.**

<b>Sr. No.</b>	<b>Description of Item(s)</b>	<b>Quantity (Approx.)</b>	<b>Rate</b>
1	Repair or replace of gutter/u-flashing or drain of Library building.	10 mtr	
2	Repair and fixing Factory made EPS light weight composite sandwiched sheet wall /roof panel (75mm thick) having core material of EPS graule balls/beds(conforming to IS4671:1984 and shall have density note less than 15kg per cum).complete as per direction of engineer-in-charge.(Note:-Outer face of Library shade at terrace floor).	20 Sqm	
3	Providing and fixing double scaffolding system (cup lock type)on the exterior side up to seven store height made with 40mm dia m.s tube 1.5m center to center horizontal &vertical tube joining with cup &lock system with m.s tube ,m.stube challies,m.s clamps and m.s stair case system in the scaffolding for working platform etc. And maintaining it in a serviceable condition for the required duration as approved and removing it thereafter the scaffolding system shall be stiffened with bracing, runner connection with the building etc wherever required for inspection of work at required locations with essential safety features. (note: ground floor to terrace floor).	20 Sqm	
4	Providing and fixing false ceiling at all height with ceiling Tiles of Armstrong make dune max RH99 or equivalent from Gyproc only 595x595mm of approved texture design and pattern, having moisture content less than 2% humidity resistance of 99% as per IS 8225:1987,non-combustibles as per BS476-1970, and galvanized @ 120gram per sqm including both side comprising of main T-runner of size 15x32 mm of length 1200mm tec . the work shall be carried out as per specification dwarfing and as per direction of engineer-in-charge.	65 Sqm	
5	Providing and fixing 1mm thickness GI sheet joint mitred with plan sheet of required size, including cutting binding and fixing and Screws and applying priming coat of approved steel primer.	80 Rmt	

	Complete as per direction of engineer-in-charge.(Note: shade covering of false ceiling at GI sheet size 300mm wide )		
<b>6</b>	Supply of ceiling Tiles of Armstrong make dune max RH99 or equivalent from Gyproc only 595x595mm of approved texture design and pattern, having moisture content less than 2% humidity resistance of 99% as per IS 8225:1987,non-combustibles as per BS476-1970,and galvanized @ 120gram per sqm including both side comprising of main T-runner of size 15x32 mm of length 1200mm tec . the work shall be carried out as per specification, dwarfing and as per direction of engineer-in-charge.(Note : Only for Supply ceiling sheet)	<b>35 No</b>	
<b>7</b>	Providing and fixing Gypsum false ceiling at all height.	<b>5 Sqm</b>	

1. Sealed envelope should be super-scribed with “Repair of False ceiling, u-shape drain, roof panel (Puff sheet), gypsum ceiling at various places in the Hansraj College” and addressed to  
**The Principal,  
Hansraj College  
Malka Ganj  
Delhi-110007**
2. Quotation should reach to the above address through Registered/Speed post or by hand latest by 24.08.2021 up to 1100Hrs and same will be open on 24.08.2021 at 1230Hrs
3. The unit rate for any item should be quoted without GST and the slab (%) or amount of GST to be mentioned therein
4. Any rate quoted by vendor without mentioning GST slab for any item, the quoted rate for that item will be considered as GST inclusive.
5. Vendors who are applying for above quotation must have GSTIN registration and GSTIN no. to be mentioned on the quotation.
6. The Principal may accept or reject any or all the quotation in part or full without assigning any reason.
7. The Principal reserve the right to splitting the items to two or more vendor for placement of order.
8. Payment Terms: Full and final payment will be made after successful delivery and installation (if required) of Instruments at free of cost at our college.
9. All the payment will be made through RTGS/NEFT only.

-Sd-  
**Convener  
Development Committee**

-Sd-  
**Principal  
Hansraj College**

**Copy to: College Website**